

Structherm | Fastbuild[®]

Easingwold

York

Sector: Keyworker & Student
Accommodation



Client:
MoD & Miller Construction

Building type:
Two 3 storey accommodation
blocks

Project size: 3418m²

Package Supplied:
Fastbuild walls, floors and roof

Build time:
23 weeks

Background:

The package provided by Structerm included Fastbuild walls, floor planks, staircases, roof structure and roof coverings. The building has been finished using Structerm's non-structural external wall insulation to the ground floor with a marble aggregate finish and timber cedar boarding to the upper floors.

Due to limited site space, deliveries were strategically worked in to the programme, with materials brought to site just in time. Bathroom pods were brought to site and installed the same day. Waste on the project was minimal as the Fastbuild system was manufactured to fit requirements. M&E was designed around the thermal mass of the concrete structure, resulting in heating requirements being reduced.

Fastbuild was chosen as it is an extremely robust product and it's construction is not weather dependent, giving predictable construction programmes. Fastbuild achieved the finished look of an arc, desired by the client rather than a faceted face, making the building more attractive.



Left & Below: Completed project

For further information on
this or other
Structerm Fastbuild™
projects please contact us on
0800 040 7460
or visit:
www.structerm.co.uk

